



Orderly

A Bewuste Bouwer (Considerate Constructor) works in an orderly manner. The construction site looks neat and tidy from the surrounding area's perspective. The construction site and the area in around the construction site are tidy and free from litter. This results in a tidy looking construction site, access roads and barriers. Materials and equipment are tidy, clean and well maintained.

Measures

As standard

- Facilities for the construction site employees and visitors are clean and well maintained.
- Materials and equipment are neatly stored, tidied up and, if necessary, covered and secured.
- Damage and pollution to roads and/or third party property will be prevented or repaired.
- Barriers are straight and the feet don't pose a falling and/or tripping risk.
- There is no notable presence of loose building- and demolition waste, litter and significant weeds on and around the construction site.

Above standard

- Facilities are tailored to the different target groups.
- Suitable waste bins are available at various locations on site.
- An alternatives to building fences which increase tidiness and uniformity is present.
- Undesirable graffiti is removed immediately.

Awareness & Communication

As standard

- The construction company encourages and facilitates the construction site employees to keep the construction site and facilities clean and tidy.
- The construction site and the surrounding area are periodically inspected.

Above standard

- Construction site employees take responsibility for keeping the site and facilities tidy themselves.
- Local residents are involved in the finishing/design of the construction site.